

				ME Collins Contracting Co., Inc.		Nemaha Landscape Construction Co.		Omaha Construction Services, Inc		Hella's Construction Inc.	
ITEM NO.	DESCRIPTION	APPROXIMATE QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
FOOTBALL FIELD SURFACING											
1	COMMON EARTH EXCAVATION	100	CY	15.00	\$1,500.00	\$ 3.92	\$392.00	\$ 3.28	328.33 \$328.00	\$ 5.60	\$560.00
2	HAUL OFF-SITE	6,100	CY	12.50	76,250.00	5.48	33,428.00	4.60	28,039.79 28,060.00	9.93	60,573.00
3	EXCAVATE UNSUITABLE MATERIAL	200	CY	10.00	2,000.00	10.57	2,114.00	8.87	1,773.01 1,774.00	5.60	1,120.00
4	REMOVE AND CAP IRRIGATION SYSTEM	1	LS	7,500.00	7,500.00	400.00	400.00	820.84	820.84	3,000.00	3,000.00
5	REMOVE GRATE INLET	15	EA	250.00	3,750.00	65.00	975.00	54.72	820.84 820.80	1,200.00	18,000.00
6	REMOVE STORM SEWER MANHOLE	1	EA	500.00	500.00	1,670.00	1,670.00	1,400.89	1,400.89	1,300.00	1,300.00
7	REMOVE STORM SEWER MANHOLE RISER SECTIONS AND COVER	1	EA	500.00	500.00	2,325.00	2,325.00	1,948.12	1,948.12	300.00	300.00
8	REMOVE AND SALVAGE GOAL POST	2	EA	2,500.00	2,500.00 5,000.00	235.00	470.00	197.00	394.00	1,000.00	2,000.00
9	CONSTRUCT RADIUS POINT MONUMENT	2	EA	350.00	700.00	223.00	446.00	218.89	437.78	1,000.00	2,000.00
10	CONSTRUCT CONCRETE CURB	760	LF	10.00	7,600.00	23.50	17,860.00	17.51	13,308.50 13,307.60	25.17	19,129.20
11	CONSTRUCT FOOTBALL FIELD, LATERAL TRENCH AND PERIMETER DRAIN TRENCH GEOTEXTILE MOISTURE BARRIER	8,900	SY	5.00	44,500.00	3.77	33,553.00	4.16	37,014.27 37,024.00	4.30	38,270.00
12	CONSTRUCT 4" PERFORATED HDPE PIPE LATERAL WITH FITTINGS AND GRAVEL FILL	3,780	LF	8.00	30,240.00	7.69	29,068.20	8.64	32,641.07 32,659.20	22.30	84,294.00
13	CONSTRUCT 12" PERFORATED HDPE COLLECTOR PIPE WITH FITTINGS AND GRAVEL FILL	935	LF	23.60	22,066.00	32.95	30,808.25	34.54	32,295.66 32,294.90	36.00	33,660.00

Engineers' Estimate: \$ 1,703,800.00
 Amount of Bid Bond: \$ 5%

PROJECT NAME: OPS - Northwest High School
 TYPE OF PROJECT: Football Field Track Reconstruction
 LRA JOB NO.: 0107112.01-026/326
 ENGINEER: Scott Loos/Joe Zadina
 BID DATE: July 8, 2008
 PAGE 2 of 5

				ME Collins Contracting Co., Inc.		Nemaha Landscape Construction Co.		Omaha Construction Services, Inc		Hella's Construction Inc.	
ITEM NO.	DESCRIPTION	APPROXIMATE QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
14	CONSTRUCT 12" STORM SEWER	8	LF	61.20	489.60	46.00	368.00	163.62	1,308.96	36.00	288.00
15	CONSTRUCT 12" STORM SEWER CONCRETE COLLAR	1	EA	310.00	310.00	390.00	390.00	674.18	674.18	400.00	400.00
16	CONSTRUCT MANHOLE RISER SECTION TO GRADE	1	LS	481.00	481.00	1,950.00	1,950.00	3,298.67	3,298.67	750.00	750.00
17	CONSTRUCT LIGHTWEIGHT MANHOLE COVER	1	EA	668.00	668.00	390.00	390.00	714.68	714.68	680.00	680.00
18	CONSTRUCT COMPOSITE PVC NAILER BOARD	1,155	LF	5.00	5,775.00	4.80	5,544.00	8.21	9,480.67 9,482.55	9.70	11,203.50
19	SUBGRADE PREPARATION	8,700	SY	1.00	8,700.00	1.83	15,921.00	1.53	13,330.39 13,311.00	3.90	33,930.00
20	CONSTRUCT AGGREGATE SUBBASE (78,250 SF @ 8" DEPTH)	8,700	SY	7.50	65,250.00	11.85	103,095.00	12.97	112,832.24 112,839.00	17.93	155,991.00
21	CONSTRUCT SYNTHETIC TURF WITH RUBBER INFILL	78,250	SF	3.44	269,180.00	3.83	299,697.50	3.19	249,589.23 249,617.50	4.77	373,252.50
22	FURNISH AND INSTALL AAE 8' OFFSET HINGED GOAL POST, BOX AND COVER	2	EA	7,000.00	14,000.00	9,895.00	19,790.00	8,648.88	47,237.77 17,297.76	10,500.00	21,000.00
TRACK RESURFACING											
1	REMOVE SYNTHETIC SURFACE AND HAUL OFF-SITE	50,600	SF	0.50	25,300.00	0.09	4,554.00	0.08	3,876.54 4,048.00	0.28	14,168.00
2	REMOVE ASPHALT (FULL DEPTH)	50,600	SF	1.00	50,600.00	0.55	27,830.00	0.53	26,581.98 26,818.00	0.50	25,300.00
3	REMOVE POLE VAULT BOX	2	EA	80.00	160.00	98.00	196.00	82.08	164.17 164.16	150.00	300.00

Engineers' Estimate: \$ 1,703,800.00
 Amount of Bid Bond: \$ 5%

PROJECT NAME: OPS - Northwest High School
 TYPE OF PROJECT: Football Field Track Reconstruction
 LRA JOB NO.: 0107112.01-026/326
 ENGINEER: Scott Loos/Joe Zadina
 BID DATE: July 8, 2008
 PAGE 3 of 5

				ME Collins Contracting Co., Inc.		Nemaha Landscape Construction Co.		Omaha Construction Services, Inc		Hella's Construction Inc.	
ITEM NO.	DESCRIPTION	APPROXIMATE QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
4	REMOVE SAND PIT AND CURBING	2	EA	150.00	300.00	456.00	912.00	383.06	766.11 766.12	985.00	1,970.00
5	REMOVE CONCRETE SIDEWALK	125	SF	1.00	125.00	1.31	163.75	1.09	136.84 136.25	8.75	1,093.75
6	REMOVE CONCRETE CURB	2,915	LF	3.00	8,745.00	2.09	6,092.35	1.75	5,104.54 5,101.25	3.00	8,745.00
7	CONSTRUCT CONCRETE CURB	1,610	LF	10.00	16,100.00	23.50	37,835.00	17.51	28,193.04 28,191.10	26.85	43,228.50
8	CONSTRUCT 4" PC CONCRETE SIDEWALK	125	SF	4.90	612.50	3.92	490.00	5.47	684.03 683.75	7.45	931.25
9	CONSTRUCT 6" PC CONCRETE PAVEMENT	300	SF	5.50	1,650.00	4.57	1,371.00	5.47	1,641.67 1,641.00	8.20	2,460.00
10	CONSTRUCT 6" REINFORCED PC CONCRETE PAVEMENT (FIELD EVENT AREA)	2,500	SY	35.00	87,500.00	39.87	99,675.00	35.95	89,881.64 89,875.00	67.20	168,000.00
11	CONSTRUCT 6" ASPHALTIC CONCRETE PAVEMENT (TRACK)	4,840	SY	15.00	72,600.00	17.62	85,280.80	16.20	78,397.58 78,408.00	20.70	100,188.00
12	ASPHALT CEMENT PERFORMANCE GRADED BINDER (PG 64-22)	90	TN	741.39	66,725.10	708.00	63,720.00	774.87	69,738.30	1,194.00	95,520.00 107,460.00
13	CONSTRUCT 6" CRUSHED LIMESTONE BASE	7,340	SY	6.25	45,875.00	7.65	56,151.00	8.37	61,454.44 61,435.80	13.18	96,741.20
14	CONSTRUCT 4" PVC CONDUIT WITH RISER SECTIONS AND THREADED CAPS	40	LF	15.80	632.00	27.69	1,107.60	15.32	612.89 612.80	5.22	208.80

Engineers' Estimate: \$ 1,703,800.00
 Amount of Bid Bond: \$ 5%

PROJECT NAME: OPS - Northwest High School
 TYPE OF PROJECT: Football Field Track Reconstruction
 LRA JOB NO.: 0107112.01-026/326
 ENGINEER: Scott Loos/Joe Zadina
 BID DATE: July 8, 2008
 PAGE 4 of 5

				ME Collins Contracting Co., Inc.		Nemaha Landscape Construction Co.		Omaha Construction Services, Inc		Hella's Construction Inc.	
ITEM NO.	DESCRIPTION	APPROXIMATE QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
15	CONSTRUCT 6" PVC CONDUIT WITH RISER SECTIONS AND THREADED CAPS	110	LF	17.40	1,914.00	30.30	3,333.00	16.42	1,806.20	6.70	737.00
16	SUBGRADE PREPARATION	7,340	SY	1.00	7,340.00	1.70	12,478.00	1.42	10,422.80	3.85	28,259.00
17	POLYURETHANE SURFACING (10 MM) WITH MARKING	66,060	SF	6.03	398,341.80	6.12	404,287.20	6.60	435,996.00	5.88	388,432.80
18	FULL DEPTH POLYURETHANE FILLING IN LOW AREAS	1,000	GAL	21.35	21,350.00	1.00	1,000.00	23.37	23,370.00	29.85	29,850.00
19	CONSTRUCT 4" PERFORATED HDPE PIPE LATERAL WITH FITTINGS AND GRAVEL FILL	1,330	LF	9.20	12,236.00	6.79	9,030.70	7.11	9,456.30	22.33	29,698.90
20	CONSTRUCT 4" NON-PERFORATED HDPE COLLECTOR PIPE WITH FITTINGS	70	LF	15.80	1,106.00	10.34	723.80	10.94	765.80	22.33	1,563.10
21	CONSTRUCT 6" NON-PERFORATED HDPE COLLECTOR PIPE WITH FITTINGS	20	LF	17.40	348.00	13.00	260.00	13.13	262.60	24.63	492.60
22	CONSTRUCT CATCH BASIN CONNECTION	4	EA	87.00	348.00	52.20	208.80	328.33	1,313.32	150.00	600.00
23	FURNISH AND INSTALL ACO SYSTEM SPORT CURBING WITH SAND TRAP	2	EA	12,500.00	25,000.00	15,660.00	31,320.00	14,991.36	29,982.72	26,113.00	52,226.00
24	FURNISH AND INSTALL ACO SPORT SYSTEM TRENCH DRAIN AND GRATE WITH CONCRETE ENCASEMENT	580	LF	48.00	27,840.00	53.00	30,740.00	73.46	42,606.80	115.43	66,949.40
25	FURNISH AND INSTALL ACO SPORT SYSTEM IN-LINE CATCH BASIN AND TRASH BUCKET	4	EA	290.00	1,160.00	528.00	2,112.00	877.75	3,511.00	179.00	716.00

Engineers' Estimate: \$ 1,703,800.00
 Amount of Bid Bond: \$ 5%

PROJECT NAME: OPS - Northwest High School
 TYPE OF PROJECT: Football Field Track Reconstruction
 LRA JOB NO.: 0107112.01-026/326
 ENGINEER: Scott Loos/Joe Zadina
 BID DATE: July 8, 2008
 PAGE 5 of 5

				ME Collins Contracting Co., Inc.		Nemaha Landscape Construction Co.		Omaha Construction Services, Inc		Hella's Construction Inc.	
ITEM NO.	DESCRIPTION	APPROXIMATE QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
26	FURNISH AND INSTALL AAE STAINLESS STEEL VAULT BOX	2	EA	1,000.00	2,000.00	783.00	1,566.00	1,307.87	2,615.73 2,615.74	1,306.00	2,612.00
27	CONSTRUCT VAULT BOX DRAIN PIPE WITH FITTINGS	45	LF	14.10	634.50	16.00	720.00	10.94	492.50 492.30	22.33	1,004.85
28	SEEDING - TYPE "TEMPORARY SEED MIX"	1	AC	393.00	393.00	1,300.00	1,300.00	383.06	383.06	11,000.00	11,000.00
29	SOD	3,000	SF	0.35	1,050.00	0.85	2,550.00	0.25	755.17 750.00	3.00	9,000.00
30	CONSTRUCT ROCK ACCESS	100	TN	29.40	2,940.00	26.00	2,600.00	21.89	2,188.90 2,189.00	216.40	21,640.00
TOTAL ALTERNATE NO. 1 BID AMOUNT											
1	CONSTRUCT CENTER LOGO	1	EA	28,939.00	28,939.00	22,000.00	22,000.00	28,600.00	28,600.00	29,644.00	29,644.00
TOTAL ALTERNATE NO. 2 BID AMOUNT											
1	BASE MAT & POLYURETHANE SURFACING (13 MM) WITH MARKING	66,060	SF	4.76	314,445.60	4.58	302,554.80	4.70	310,534.85 310,482.00	5.73	378,523.80
TOTAL BASE BID AMOUNT					\$1,447,885.50		1,490,262.25 \$1,490,262.95		1,494,773.72 \$1,493,357.60		2,077,165.75 \$2,077,277.35

Engineers' Estimate: \$ 1,703,800.00
 Amount of Bid Bond: \$ 5%