

EPPLEY AIRFIELD
 EXTEND TAXIWAY S NORTH AND RECONSTRUCT TAXIWAY L
 FAA AIP 3-31-0062-54
 LRA JOB NO. 08102.01-120

BID DATE: MARCH 3, 2010

BID TABS

ITEM NO.	A.C. ITEM NO.	ITEM DESCRIPTION	APPROXIMATE QUANTITY	ENGINEERS ESTIMATE		Hawkins Construction Co	
				Unit Price	Amount	Unit Price	Amount
1	P-101-5.1	Remove Asphaltic Concrete Pavement	8,889 SY	\$6.00	\$53,334.00	\$4.23	\$37,600.47
2	P-101-5.2	Remove Portland Cement Concrete Pavement	29,288 SY	\$8.00	\$234,304.00	\$3.84	\$112,465.92
3	P-101-5.3	Cold Milling Asphalt Pavement	474 SY	\$7.00	\$3,318.00	\$21.56	\$10,219.44
4	P-101-5.4	Remove Storm Sewer Pipe	3,397 LF	\$10.00	\$33,970.00	\$9.99	\$33,936.03
5	P-101-5.5	Crush VCP <10" in Place	100 LF	\$8.00	\$800.00	\$2.86	\$286.00
6	P-101-5.6	Remove Storm Sewer Inlet/Manhole	16 EA	\$600.00	\$9,600.00	\$217.79	\$3,484.64
7	P-101-5.7	Saw-Cut PCC Pavement	1,366 LF	\$8.00	\$10,928.00	\$9.33	\$12,744.78
8	P-101-5.8	Saw-Cut ACC Pavement	368 LF	\$7.00	\$2,576.00	\$4.09	\$1,505.12
9	P-101-5.9	Remove 6" Underdrain Pipe	2,506 LF	\$4.00	\$10,024.00	\$1.12	\$2,806.72
10	P-101-5.10	Remove Underdrain Inspection Hole	10 EA	\$150.00	\$1,500.00	\$101.96	\$1,019.60
11	P-101-5.11	Adjust Area Inlet/Manhole to Grade	4 EA	\$1,000.00	\$4,000.00	\$486.54	\$1,946.16
12	P-101-5.12	Remove Access Road	3,042 SY	\$6.00	\$18,252.00	\$3.84	\$11,681.28
13	P-101-5.13	Asphalt Millings for Access Roads, 6" Thick	235 SY	\$5.00	\$1,175.00	\$2.33	\$547.55
14	P-101-5.14	Construct Concrete Mow Strip	25 LF	\$15.00	\$375.00	\$29.60	\$740.00
15	P-101-5.15	Construct Temporary Taxiway Edge Light Mounted on Bucket Barricade	25 EA	\$500.00	\$12,500.00	\$1,032.47	\$25,811.75
16	P-101-5.16	Construct Temporary Barricade with Light	200 EA	\$125.00	\$25,000.00	\$92.10	\$18,420.00
17	P-101-5.17	Furnish and Install Limits of Construction Fencing	14,100 LF	\$4.00	\$56,400.00	\$3.97	\$55,977.00
18	P-101-5.18	Install Owner Furnished Limits of Construction Fencing	7,050 LF	\$2.00	\$14,100.00	\$1.62	\$11,421.00
19	P-102-4.2	Radio Equipped Safety Escort	100 HR	\$60.00	\$6,000.00	\$60.00	\$6,000.00
20	P-102-4.3.1	Initial Mobilization - Phase 1	1 LS	\$260,000.00	\$260,000.00	\$260,000.00	\$260,000.00
21	P-102-4.3.2	Initial Mobilization - Phase 2	1 LS	\$90,000.00	\$90,000.00	\$90,000.00	\$90,000.00
22	P-102-4.3.3	Initial Mobilization - Phase 3	1 LS	\$280,000.00	\$280,000.00	\$280,000.00	\$280,000.00
23	P-102-4.3.4	Initial Mobilization - Phase 4	1 LS	\$60,000.00	\$60,000.00	\$60,000.00	\$60,000.00
24	P-102-4.3.5	Initial Mobilization - Phase 5	1 LS	\$190,000.00	\$190,000.00	\$190,000.00	\$190,000.00
25	P-152-4.1	Unclassified Excavation	134,262 CY	\$8.00	\$1,074,096.00	\$4.39	\$589,410.18
26	P-152-4.2	Crushed Rock for Subgrade Stabilization	550 TN	\$30.00	\$16,500.00	\$32.57	\$17,913.50
27	P-152-4.3	Exploratory Excavation	100 HR	\$200.00	\$20,000.00	\$191.34	\$19,134.00
28	P-153-7.1	Controlled Low Strength Material	35 CY	\$150.00	\$5,250.00	\$98.09	\$3,433.15
29	P-154-5.1.1	18-inch Subbase Course	48,245 SY	\$12.00	\$578,940.00	\$8.07	\$389,337.15
30	P-154-5.1.2	17-inch Subbase Course	35,021 SY	\$12.00	\$420,252.00	\$7.99	\$279,817.79
31	P-154-5.1.3	25-Inch to 33-Inch Subbase Course	17,798 SY	\$16.00	\$284,768.00	\$13.22	\$235,289.56
32	P-154-5.1.4	26-Inch to 34-Inch Subbase Course	13,915 SY	\$16.00	\$222,640.00	\$13.87	\$193,001.05
33	P-154-5.1.5	4-Inch to 30-Inch Subbase Course	400 SY	\$15.00	\$6,000.00	\$8.08	\$3,232.00
34	P-154-5.2	Filter Fabric for Subgrade Course	114,979 SY	\$1.50	\$172,468.50	\$1.25	\$143,723.75
35	P-154-5.3	Stabilization Fabric for Subgrade Course	4,514 SY	\$1.50	\$6,771.00	\$1.01	\$4,559.14
36	P-156-5.1.1	Install and Remove Temporary Silt Fence	200 LF	\$5.00	\$1,000.00	\$1.92	\$384.00
37	P-156-5.1.2	Construct and Remove Temporary Silt Fence for Area Inlets	62 EA	\$100.00	\$6,200.00	\$54.82	\$3,398.84
38	P-156-5.1.3	Construct and Remove Double Silt Fence for Area Inlets	62 EA	\$200.00	\$12,400.00	\$153.50	\$9,517.00
39	F-162-5.1	Reconstruct 8' Chain-Link Fence from Salvaged Material	25 LF	\$75.00	\$1,875.00	\$26.31	\$657.75
40	F-162-5.2	Remove and Salvage 8' Chain-Link Fence	25 LF	\$15.00	\$375.00	\$26.31	\$657.75
41	F-162-5.3	Construct and Remove Temporary 8' Chain-Link Swing Gate	1 EA	\$2,000.00	\$2,000.00	\$2,028.49	\$2,028.49
42	P-207-4.1.1	8" Crushed Aggregate Base Course	39,588 SY	\$10.00	\$395,880.00	\$8.33	\$329,768.04
43	P-207-4.1.2	4" Crushed Aggregate Base Course	4,279 SY	\$8.50	\$36,371.50	\$4.64	\$19,854.56
44	P-208-5.1	6" Crushed Aggregate Base Course for PCC Pavement	83,266 SY	\$12.00	\$999,192.00	\$8.91	\$741,900.06
45	P-304-8.1	6" Cement Treated Base Course	83,266 SY	\$18.00	\$1,498,788.00	\$11.85	\$986,702.10
46	P-402-11.1	Bituminous Surface Course	45 TN	\$250.00	\$11,250.00	\$361.84	\$16,282.80
47	P-403-11.1	4" Bituminous Surface Course	41,508 SY	\$30.00	\$1,245,240.00	\$21.38	\$887,441.04
48	P-501-8.1.1	17" Plain or Reinforced Portland Cement Concrete Pavement	31,799 SY	\$85.00	\$2,702,915.00	\$76.00	\$2,416,724.00
49	P-501-8.1.2	15" Plain or Reinforced Portland Cement Concrete Pavement	45,035 SY	\$80.00	\$3,602,800.00	\$70.64	\$3,181,272.40
50	P-501-8.1.3	7" to 13" Plain or Reinforced Portland Cement Concrete Pavement	400 SY	\$75.00	\$30,000.00	\$60.00	\$24,000.00
51	P-603-5.1	Bituminous Tack Coat	850 GL	\$8.00	\$6,800.00	\$4.66	\$3,961.00
52	P-620-5.1.1	Runway and Taxiway Painting with Reflective Media - Yellow	53,889 SF	\$1.25	\$67,361.25	\$0.84	\$45,266.76
53	P-620-5.1.2	Runway and Taxiway Painting - Black Outline	44,534 SF	\$1.25	\$55,667.50	\$0.79	\$35,181.86
54	P-620-5.1.3	Runway and Taxiway Painting with Reflective Media - White	4,194 SF	\$1.25	\$5,242.50	\$0.90	\$3,774.60
55	P-620-5.1.4	Taxiway Painting with Reflective Media Epoxy - Red	2,488 SF	\$5.00	\$12,440.00	\$6.25	\$15,550.00
56	P-620-5.1.5	Temporary Taxiway Painting - White/Yellow	1,976 SF	\$1.00	\$1,976.00	\$0.66	\$1,304.16
57	P-620-5.1.6	Access Road Painting - White	192 SF	\$15.00	\$2,880.00	\$3.29	\$631.68
58	P-620-5.1.7	Taxiway Painting with Reflective Media Epoxy - White	808 SF	\$1.25	\$1,010.00	\$0.79	\$638.32
59	P-620-5.1.8	Taxiway Painting with Reflective Media Epoxy - Black	261 SF	\$1.25	\$326.25	\$0.79	\$206.79
60	P-620-5.2	Runway and Taxiway Painting Removal	23,742 SF	\$1.50	\$35,613.00	\$0.99	\$23,504.58
61	D-701-5.1.1	12" CMP Storm Sewer	50 LF	\$30.00	\$1,500.00	\$48.01	\$2,400.50
62	D-701-5.1.2	18" RCP Storm Sewer (Class III)	1,090 LF	\$35.00	\$38,150.00	\$23.70	\$25,833.00
63	D-701-5.1.3	24" RCP Storm Sewer (Class III)	1,601 LF	\$40.00	\$64,040.00	\$32.14	\$51,456.14
64	D-701-5.1.4	30" RCP Storm Sewer (Class III)	1,845 LF	\$55.00	\$101,475.00	\$46.18	\$85,202.10
65	D-701-5.1.5	30" RCP Storm Sewer (Class IV)	283 LF	\$60.00	\$16,980.00	\$50.70	\$14,348.10
66	D-701-5.1.6	54" RCP Storm Sewer (D0.01=1350 lb.)	201 LF	\$140.00	\$28,140.00	\$95.89	\$19,273.89
67	D-701-5.1.7	54" RCP Storm Sewer (D0.01=2000 lb.)	320 LF	\$150.00	\$48,000.00	\$115.95	\$37,104.00
68	D-701-5.1.8	60" RCP Storm Sewer (D0.01=1350 lb.)	336 LF	\$190.00	\$63,840.00	\$118.76	\$39,903.36
69	D-701-5.1.9	60" RCP Storm Sewer (D0.01=2000 lb.)	495 LF	\$200.00	\$99,000.00	\$164.15	\$81,254.25
70	D-701-5.2.1	Crushed Rock Bedding for 12" CMP	50 LF	\$10.00	\$500.00	\$10.71	\$535.50
71	D-701-5.2.2	Crushed Rock Bedding for 18" RCP	1,090 LF	\$15.00	\$16,350.00	\$12.54	\$13,668.60
72	D-701-5.2.3	Crushed Rock Bedding for 24" RCP	1,601 LF	\$20.00	\$32,020.00	\$17.61	\$28,193.61

ITEM NO.	A.C. ITEM NO.	ITEM DESCRIPTION	APPROXIMATE QUANTITY	ENGINEERS ESTIMATE		Hawkins Construction Co		
				Unit Price	Amount	Unit Price	Amount	
73	D-701-5.2.4	Crushed Rock Bedding for 30" RCP	2,128	LF	\$24.00	\$51,072.00	\$37.45	\$79,693.60
74	D-701-5.2.5	Crushed Rock Bedding for 54" RCP	521	LF	\$42.00	\$21,882.00	\$108.01	\$56,273.21
75	D-701-5.2.6	Crushed Rock Bedding for 60" RCP	831	LF	\$48.00	\$39,888.00	\$157.70	\$131,048.70
76	D-701-5.3	Crushed Rock for Trench Stabilization With Fabric	225	TN	\$32.00	\$7,200.00	\$31.15	\$7,008.75
77	D-701-5.4	Cast-In-Place Pipe Plug	9	EA	\$650.00	\$5,850.00	\$557.11	\$5,013.99
78	D-701-5.5	Construct 30" Pipe Collar	1	EA	\$800.00	\$800.00	\$492.50	\$492.50
79	D-701-5.6	12" CMP Flared End Section	2	EA	\$250.00	\$500.00	\$134.14	\$268.28
80	D-701-5.7	Reconnect Storm Sewer With Collars	1	EA	\$1,600.00	\$1,600.00	\$492.50	\$492.50
81	D-705-5.1	6" Perforated Pipe Underdrain System	15,991	LF	\$12.00	\$191,892.00	\$11.20	\$179,099.20
82	D-705-5.2	Construct Underdrain Backflow Preventer	14	EA	\$1,650.00	\$23,100.00	\$1,496.16	\$20,946.24
83	D-705-5.3	Tap Underdrain into Storm Sewer Pipe	4	EA	\$350.00	\$1,400.00	\$214.85	\$859.40
84	D-705-5.4	6" Underdrain Pipe Connection to Storm Sewer Inlet/Manhole	14	EA	\$300.00	\$4,200.00	\$214.85	\$3,007.90
85	D-751-5.1.1	Single Grate 54" Area Inlet	17	EA	\$4,400.00	\$74,800.00	\$4,004.67	\$68,079.39
86	D-751-5.1.2	Single Grate 96" Area Inlet	2	EA	\$10,000.00	\$20,000.00	\$9,901.92	\$19,803.84
87	D-751-5.1.3	Single Grate 108" Area Inlet	5	EA	\$16,000.00	\$80,000.00	\$12,915.63	\$64,578.15
88	D-751-5.1.4	Construct 108" I.D. Flattop Manhole	1	EA	\$18,000.00	\$18,000.00	\$94,869.46	\$94,869.46
89	D-751-5.1.5	Underdrain Inspection Holes	73	EA	\$750.00	\$54,750.00	\$647.04	\$47,233.92
90	D-751-5.2	Pipe Connection To Existing Inlet/Manhole	1	EA	\$1,400.00	\$1,400.00	\$619.04	\$619.04
91	D-751-5.3	Remove Pipe Plug and Connect to Existing Pipe	1	EA	\$900.00	\$900.00	\$515.97	\$515.97
92	T-901-5.1.1	Drill Seeding	85	AC	\$750.00	\$63,750.00	\$466.00	\$39,610.00
93	T-901-5.1.2	Temporary Seeding	85	AC	\$125.00	\$10,625.00	\$43.86	\$3,728.10
94	T-905-5.1	Strip, Stockpile and Respread Topsoil	34,550	CY	\$2.50	\$86,375.00	\$1.64	\$56,662.00
95	T-905-5.2	Strip and Waste Topsoil	13,350	CY	\$2.50	\$33,375.00	\$1.64	\$21,894.00
96	T-905-5.3	Strip, Stockpile and Respread Topsoil -- Waste Area	17,750	CY	\$2.50	\$44,375.00	\$1.64	\$29,110.00
97	T-905-5.4	Strip & Respread Topsoil	3,875	CY	\$2.50	\$9,687.50	\$1.10	\$4,262.50
98	U-1202-7.1	Construct 10-Inch Ductile Iron Water Main	395	LF	\$70.00	\$27,650.00	\$81.13	\$32,046.35
99	U-1202-7.2	Tap Into Existing Water Main	2	EA	\$1,500.00	\$3,000.00	\$2,532.86	\$5,065.72
100	U-1202-7.3	Construct 16" Steel Casing	211	LF	\$85.00	\$17,935.00	\$82.23	\$17,350.53
101	U-1202-7.4	Construct 10" 45 Degree Bend	4	EA	\$600.00	\$2,400.00	\$722.59	\$2,890.36
102	U-1202-7.5	Construct 12" Water Main Crossing	1	EA	\$11,000.00	\$11,000.00	\$7,933.03	\$7,933.03
103	U-1202-7.6	Remove 10" Water Main	382	LF	\$10.00	\$3,820.00	\$15.35	\$5,863.70
104		Construct 6" Ductile Iron Sewer Pipe	340	LF	\$95.00	\$32,300.00	\$76.75	\$26,095.00
105		Tap into Existing Sanitary Main	4	EA	\$500.00	\$2,000.00	\$1,413.35	\$5,653.40
106		Construct 6" - 45 Degree Bend	8	EA	\$500.00	\$4,000.00	\$616.22	\$4,929.76
107		Construct 14" Steel Casing	171	LF	\$70.00	\$11,970.00	\$62.50	\$10,687.50
108		Construct Cleanout	3	EA	\$1,800.00	\$5,400.00	\$2,124.99	\$6,374.97
109		Remove Existing Sanitary Main	315	LF	\$15.00	\$4,725.00	\$15.35	\$4,835.25
110		Lift Station Pumping	4	DY	\$3,000.00	\$12,000.00	\$3,175.11	\$12,700.44
111		Remove Guidance Sign, Pad & Base, Complete	32	EA	\$170.00	\$5,440.00	\$83.88	\$2,684.16
112		Remove Runway/Taxiway Light and Transformer, Complete	196	EA	\$63.00	\$12,348.00	\$48.19	\$9,445.24
113		Remove Field Lighting Pull Box	4	EA	\$65.00	\$260.00	\$219.28	\$877.12
114		Remove Cable from Existing Duct	9,000	LF	\$0.25	\$2,250.00	\$0.41	\$3,690.00
115		L-867 Base w/Solid Cover, Installed	10	EA	\$820.00	\$8,200.00	\$823.45	\$8,234.50
116		L-868B Base w/Solid Cover for Future In-pavement Light, Installed	165	EA	\$1,300.00	\$214,500.00	\$954.27	\$157,454.55
117		L-804 Guard Light on L-867 Base w/Transf, Installed	8	EA	\$2,400.00	\$19,200.00	\$2,752.16	\$22,017.28
118		L-852G Guard Light in L-868 Base w/Transf, Installed	24	EA	\$1,800.00	\$43,200.00	\$1,810.29	\$43,446.96
119		Reinstall Existing Runway/Taxiway Elevated Fixture w/Transf. on New L-867 Base, Complete	3	EA	\$950.00	\$2,850.00	\$843.19	\$2,529.57
120		Reinstall Existing Runway/Taxiway In-pavement Fixture w/Transf. in New L-868 Base, Complete	22	EA	\$1,200.00	\$26,400.00	\$924.83	\$20,346.26
121		L-861 Taxiway Edge Light w/Transf. on Existing L-867 Base, Installed	11	EA	\$500.00	\$5,500.00	\$375.82	\$4,134.02
122		L-861 Taxiway Edge Light on L-867 Base w/Transf, Installed	213	EA	\$1,200.00	\$255,600.00	\$1,129.65	\$240,615.45
123		Bucket Mounted L-861 Taxiway Edge Light w/Transf, Installed	4	EA	\$300.00	\$1,200.00	\$270.28	\$1,081.12
124		L-852C/D Taxiway Centerline Light w/Transf in Existing L-868 Base, Installed	311	EA	\$850.00	\$264,350.00	\$475.87	\$147,995.57
125		L-852C/D Taxiway Centerline Light in L-868 Base w/Transf, Installed	107	EA	\$1,700.00	\$181,900.00	\$1,330.79	\$142,394.53
126		L-850C Runway Semi-flush Edge Light & Transf. in L-868 Base w/Existing Control Module, Installed	1	EA	\$1,200.00	\$1,200.00	\$684.05	\$684.05
127		Reinstall Existing Guidance Sign, Size 4, 1-Module, Complete	1	EA	\$800.00	\$800.00	\$225.65	\$225.65
128		Reinstall Existing Guidance Sign, Size 3, 1-Module, Complete	1	EA	\$600.00	\$600.00	\$225.65	\$225.65
129		L-858 Guidance Sign, Size 3, 1-Module w/ Transformer, Installed	6	EA	\$1,900.00	\$11,400.00	\$1,599.50	\$9,597.00
130		L-858 Guidance Sign, Size 2, 4-Module w/ Transformer, Installed	8	EA	\$3,800.00	\$30,400.00	\$4,023.75	\$32,190.00
131		L-858 Guidance Sign, Size 2, 3-Module w/ Transformer, Installed	16	EA	\$3,000.00	\$48,000.00	\$3,107.64	\$49,722.24
132		L-858 Guidance Sign, Size 2, 2-Module w/ Transformer, Installed	10	EA	\$2,400.00	\$24,000.00	\$2,216.36	\$22,163.60
133		L-858 Guidance Sign, Size 2, 1-Module w/ Transformer, Installed	3	EA	\$1,800.00	\$5,400.00	\$1,540.66	\$4,621.98
134		Guidance Sign Pad & L-867 Base, Size 4, 1-Module, Installed	1	EA	\$1,600.00	\$1,600.00	\$1,374.43	\$1,374.43
135		Guidance Sign Pad & L-867 Base, Size 3, 1-Module, Installed	7	EA	\$1,600.00	\$11,200.00	\$1,374.43	\$9,621.01
136		Guidance Sign Pad & L-867 Base, Size 2, 4-Module, Installed	8	EA	\$1,800.00	\$14,400.00	\$1,596.48	\$12,771.84
137		Guidance Sign Pad & L-867 Base, Size 2, 3-Module, Installed	14	EA	\$1,700.00	\$23,800.00	\$1,531.23	\$21,437.22
138		Guidance Sign Pad & L-867 Base, Size 2, 2-Module, Installed	9	EA	\$1,600.00	\$14,400.00	\$1,439.01	\$12,951.09
139		Guidance Sign Pad & L-867 Base, Size 2, 1-Module, Installed	3	EA	\$1,600.00	\$4,800.00	\$1,374.43	\$4,123.29
140		Extend Existing Guidance Sign Pad, Complete	3	EA	\$400.00	\$1,200.00	\$316.23	\$948.69
141		Field Lighting Pull Box (24"x24")	30	EA	\$800.00	\$24,000.00	\$600.05	\$18,001.50
142		Fiber Pull Box (30"x48"x36"D)	4	EA	\$2,000.00	\$8,000.00	\$2,486.50	\$9,946.00
143	L-110-5.1	2" RGS Conduit Under Existing Pavement, Installed	350	LF	\$18.00	\$6,300.00	\$15.92	\$5,572.00
144	L-110-5.1	2" PVC40 Conduit, Installed	43,375	LF	\$1.80	\$78,075.00	\$1.67	\$72,436.25
145	L-110-5.2	2" PVC40 Concrete Encased Conduit, Installed	12,020	LF	\$7.50	\$90,150.00	\$4.74	\$56,974.80

ITEM NO.	A.C. ITEM NO.	ITEM DESCRIPTION	APPROXIMATE QUANTITY		ENGINEERS ESTIMATE		Hawkins Construction Co	
					Unit Price	Amount	Unit Price	Amount
146	L-110-5.1	2" 15-Way Concrete Encased Duct Bank, incl. Trenching, Backfill and Warning Tape, Installed	300	LF	\$65.00	\$19,500.00	\$80.26	\$24,078.00
147	L-110-5.1	3" Split PVC40 Conduit, Concrete Encased, Installed	380	LF	\$28.00	\$10,640.00	\$13.29	\$5,050.20
148	L-110-5.1	4" HDPE Conduit, Installed	2,370	LF	\$5.00	\$11,850.00	\$5.19	\$12,300.30
149	L-110-5.1	3" RGS Conduit, Installed	100	LF	\$16.00	\$1,600.00	\$19.59	\$1,959.00
150	L-110-5.1	4" RGS Conduit, Installed	280	LF	\$25.00	\$7,000.00	\$15.17	\$4,247.60
151	L-108-5.1	Trenching & Backfill 18-24" Deep, Complete	27,325	LF	\$2.10	\$57,382.50	\$2.06	\$56,289.50
152	L-108-5.1	Trenching & Backfill 48" Deep, Complete	2,650	LF	\$3.50	\$9,275.00	\$2.17	\$5,750.50
153	L-108-5.4	Counterpoise System for Field Lighting, Installed	24,100	LF	\$1.20	\$28,920.00	\$1.10	\$26,510.00
154	L-108-5.5	Safety Ground System for Field Lighting, Installed	34,585	LF	\$1.30	\$44,960.50	\$1.07	\$37,005.95
155		RWIS Cable, Installed	380	LF	\$3.50	\$1,330.00	\$4.05	\$1,539.00
156	L-108-5.2	1/C, #6, 5 KV, L-824 Cable, Installed	12,350	LF	\$1.65	\$20,377.50	\$1.20	\$14,820.00
157	L-108-5.3	1/C, #8, 5 KV, L-824 Cable, Installed	116,600	LF	\$1.50	\$174,900.00	\$0.89	\$103,774.00
158	L-110	Concrete Duct Marker, In Place	13	EA	\$130.00	\$1,690.00	\$232.45	\$3,021.85
159	L-109-5.1	4kW L-828, 5.5A, 1-Step, Saturable Reactor Regulator, Installed	1	EA	\$10,000.00	\$10,000.00	\$8,435.21	\$8,435.21
160	L-109-5.1	East Field Lighting Vault Electrical Work, Complete	1	LS	\$5,200.00	\$5,200.00	\$2,486.81	\$2,486.81
161		Airfield Lighting Control System (ALCS) Modifications for Taxiway S, Complete	1	EA	\$18,000.00	\$18,000.00	\$7,675.35	\$7,675.35
162		Airfield Lighting Control System (ALCS) Modifications for Taxiway L, Complete	1	EA	\$18,000.00	\$18,000.00	\$7,675.35	\$7,675.35
163		Spare Parts for Taxiway S	1	LS	\$1,200.00	\$1,200.00	\$822.36	\$822.36
164		Spare Parts for Taxiway L	1	LS	\$1,200.00	\$1,200.00	\$822.36	\$822.36
165		Relocate Existing Light Poles	1	LS	\$10,000.00	\$10,000.00	\$1,099.56	\$1,099.56
						\$18,313,009.50		\$14,819,945.43
					** Estimate includes Addendums 1 & 2			