

ADDENDUM NO. 1
TO PLANS, SPECIFICATIONS AND CONTRACT DOCUMENTS

TO: ALL PLANHOLDERS AND PROSPECTIVE BIDDERS

FOR: RALSTON PUBLIC SCHOOLS
MEADOWS ELEMENTARY SCHOOL
LRA JOB NO. 0109112.01-021/321

OWNER: RALSTON PUBLIC SCHOOLS

ENGINEER: LAMP, RYNEARSON & ASSOCIATES, INC.
14710 WEST DODGE ROAD, SUITE 100
OMAHA, NEBRASKA 68154-2027

DATE: MAY 10, 2010

The following changes, corrections, clarifications and additions shall be made to the Plans, Specifications, and Contract Documents for the above-named project and shall be as binding as if incorporated in the original Contract Documents. The Contractor shall acquaint himself with all aspects of this Addendum.

All other provisions and stipulations of the Contract Documents remain in effect, as originally issued.

The Contractor shall acknowledge receipt of all addenda on the Proposal Form.

The following shall be deleted, modified or added to as follows:

PLANS

1. Sheet 5 of 9 – Modify Storm Sewer key notes per updated attached sheet.
2. Sheet 8 of 9 - Flag note #2 – clarification: Contractor shall provide shop drawing submittal for lighting relay panel. Contractor shall provide owner training for operation and programming of relay panel. If any specialized equipment/software is required to program the relay panel, the contractor shall provide the district with that equipment/software. Contractor shall verify programming with owner. Greengate LK8 shall be considered as equal to product specified.
3. Sheet 9 of 9 - The following fixtures shall be considered as equal to those specified in the light fixture schedule subject to compliance with Omaha Lighting ordinance (calculations to be included with fixture submittal)
'A' – Invue EXM series
'B' – Invue EXM series

CONTRACT DOCUMENTS

1. Modify items 19-22 to be 10" in the following bid item tables NOTICE TO CONTRACTORS; BID FORM; AGREEMENT and CONTRACTORS APPLICATION FOR PAYMENT.
2. Add item 41, **CONSTRUCT PVC INLINE DRAIN WITH 24" PEDESTRIAN LIGHT DUTY GRATE.**
3. Sheet SpC-11. Modify note 11 to the following:
11. **CONSTRUCT " FLARED END SECTION:** At the location shown on the PLANS, the CONTRACTOR shall construct a flared end section. Flared end section material shall match storm sewer materials. **A 10"x12" reducer shall be used to connect 10" storm sewer to 12" Flared End Section. The 10" reducer shall be considered incidental to "Construct ___" Flared End Section.** Payment for the bid item "Construct ___" Flared

End Section" shall be of the contract unit price per each and shall include full compensation for all labor, tools, material and equipment necessary or incidental for the construction of the flared end section.

4. Sheet SpC-11. Add note 12:


- 12. CONSTRUCT PVC INLINE DRAIN WITH 24" PEDESTRIAN LIGHT DUTY GRATE: At the location shown on the PLANS, the CONTRACTOR shall construct a PVC Inline Drain with a 24" Pedestrian Light Duty Grate. The inline grate shall be ADS Nyloplast or approved equivalent. The 24" pedestrian rated light duty grate shall be considered incidental to inline drain. Payment for the bid item "Construct PVC Inline drain with 24" Pedestrian Light Duty Grate shall be at the contract unit price per each and shall include full compensation for all labor, tools, materials and equipment necessary or incidental for the construction of a PVC Inline Drain with a 24" Pedestrian Light Duty Grate.**

ENCLOSURES

END OF ADDENDUM

Sincerely,

LAMP, RYNEARSON & ASSOCIATES, INC.



Patrick C. Hillyer, P.E., LEED® AP
Senior Project Engineer