

ADDENDUM NO. 1
TO PLANS, SPECIFICATIONS AND CONTRACT DOCUMENTS

TO: ALL PLANHOLDERS AND PROSPECTIVE BIDDERS

FOR: SANITARY & IMPROVEMENT DISTRICT NO. 264
(SHADOW LAKE)
SILT BASIN REMOVAL 1, 2 & 3
LRA JOB NO. 0104031.11-042/342

OWNER: S.I.D. NO. 264 OF SARPY COUNTY, NEBRASKA

ENGINEER: LAMP, RYNEARSON & ASSOCIATES, INC.
14710 WEST DODGE ROAD, SUITE 100
OMAHA, NEBRASKA 68154-2029

DATE: SEPTEMBER 14, 2009

The following changes, corrections, clarifications and additions shall be made to the Plans, Specifications, and Contract Documents for the above-named project and shall be as binding as if incorporated in the original Contract Documents. The Contractor shall acquaint himself with all aspects of this Addendum.

All other provisions and stipulations of the Contract Documents remain in effect, as originally issued.

The Contractor shall acknowledge receipt of all addenda on the Proposal Form.

The following shall be deleted, modified or added to as follows:

PLANS

Note 1 in the General notes on Sheet 2 of 7 of the plans shall be revised to read as follows:

1. The time limit to complete all work shall be TWENTY FIVE (25) working days.

On Sheet 2 of 7, the note with a border around it, adjacent to the "Stockpile Location", shall be revised to read as follows:

The CONTRACTOR Shall Keep the Stockpile Area in Good Shape and Seed Disturbed Area with Temporary Seed. Straw Mulch Shall Be Crimped In Place Over Temporary Seed Areas.

Grading keynotes 1, 9 and 17 on Sheet 3 of 7 shall be revised to read as follows:

1. Cleanout Manhole and Remove Pipe Plug. Cleanout Shall Be Incidental To Removal Of The Pipe Plug.
9. Cleanout Curb Inlet and Remove Pipe Plug. Cleanout Shall Be Incidental To Removal Of The Pipe Plug.
17. Cleanout Curb Inlet and Remove Pipe Plug. Cleanout Shall Be Incidental To Removal Of The Pipe Plug.

Delete from the drawing the text label "area inlet rim = XXXX" at the locations designated by Grading Keynotes 4, 12, and 20 on Sheet 3 of 7.

S.I.D. No. 264 (Shadow Lake
 Addendum No. 1
 Silt Basins Removal 1, 2 & 3
 LRA Job No. 0104031.11-042/342
 September 14, 2009
 Page 2

Add 200 linear feet of silt fence to the plan view of Silt Basin 1 on Sheet 3 of 7. The silt fence shown will be extended approximately 110 linear feet along the east property line of Lot 261 and 90 linear feet along the west property line of Lot 259.

Add 150 linear feet of silt fence to the plan view of Silt Basin 2 on Sheet 3 of 7. The silt fence shown will be extended approximately 80 linear feet will be extended along the north property line of Lot 253 and 70 linear feet along the south property line of Lot 252.

Add 60 linear feet of silt fence to the plan view of Silt Basin 3 on Sheet 3 of 7. The silt fence shown will be extended approximately 20 linear feet along the west property line of Lot 13 and 40 linear feet along the south property line of Lot 15.

CONTRACT DOCUMENTS

The bid date has been changed from September 16, 2009 to October 7, 2009. Reference to the bid date on pages NC-1 (Notice to Contractors) and BB-1(Bid Bond) of the Contract Documents shall be revised to reflect the October 7, 2009 bid date.

Add Bid Item No. 26 "Temporary Seed" to the bid item table and Paragraph 2 of Item 2c in Section F (SEEDING) of the Special Conditions the Contract Documents.

Replace the bid item tables in the Notice to Contractor, Pages NC-1 to NC-2; Bid Items, Pages B-1 to B-6 10; *Sample* Agreement, Pages A-1 to A-8; and Contractor's Application for Payment with the following revised bid item table.

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
1.	STRIP, STOCKPILE AND RESPREAD TOPSOIL (ESTABLISHED QUANTITY - 1300 CY X 2 = 2600 CY)	2,600	CY
2.	COMMON EARTH EXCAVATION - ON LOT (ESTABLISHED QUANTITY)	2,740	CY
3.	COMMON EARTH EXCAVATION - FROM STOCKPILE (ESTABLISHED QUANTITY)	6,830	CY
4.	CLEANOUT SILT BASIN (ESTABLISHED QUANTITY)	1,930	CY
5.	EXCAVATE UNSUITABLE MATERIAL	1,430	CY
6.	OVEREXCAVATION BACKFILL - FROM STOCKPILE	700	CY
7.	REMOVE SILT BASIN RISER AND OUTLET PIPE (BASIN NO. 1)	1	LS
8.	REMOVE SILT BASIN RISER AND OUTLET PIPE (BASIN NO. 2)	1	LS
9.	REMOVE SILT BASIN RISER AND OUTLET PIPE (BASIN NO. 3)	1	LS
10.	REMOVE 18" TO 30" PIPE PLUG	3	EA
11.	REMOVE 21" DIVERSION PIPE	65	LF
12.	REMOVE 24" DIVERSION PIPE	85	LF
13.	REMOVE 27" DIVERSION PIPE	75	LF
14.	CONSTRUCT 21" PIPE PLUG	1	EA
15.	CONSTRUCT 24" PIPE PLUG	1	EA
16.	CONSTRUCT 27" PIPE PLUG	1	EA

S.I.D. No. 264 (Shadow Lake
Addendum No. 1
Silt Basins Removal 1, 2 & 3
LRA Job No. 0104031.11-042/342
September 14, 2009
Page 3

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
17.	REMOVE AND REPLACE 6" PC CONCRETE TRAIL	130	SF
18.	CONSTRUCT GEOGRID	970	SY
19.	CONSTRUCT GEOTEXTILE FABRIC	970	SY
20.	RECYCLED CONCRETE	260	TN
21.	FLOWABLE FILL	12	CY
22.	NON-IRRIGATED LAWN AND TURF SEED	2.8	AC
23.	STRAW MULCH	6.5	AC
24.	CONSTRUCT EROSION CONTROL BLANKET	800	SY
25.	CONSTRUCT SILT FENCE	995	LF
26.	TEMPORARY SEED	3.7	AC

A REVISED BID FORM IS ENCLOSED.

ENCLOSURES

END OF ADDENDUM

Sincerely,

LAMP, RYNEARSON & ASSOCIATES, INC.

David G. Lampe, P.E., LEED AP®
Sustainable Design Specialist