

ADDENDUM NO. 2
TO PLANS, SPECIFICATIONS AND CONTRACT DOCUMENTS

TO: ALL PLANHOLDERS AND PROSPECTIVE BIDDERS

FOR: SANITARY & IMPROVEMENT DISTRICT NO. 290
(SCHEWE FARMS, PAVING SECTION I)
LRA JOB NO. 0109050.11-050

OWNER: S.I.D. NO. 290 OF SARPY COUNTY, NEBRASKA

ENGINEER: LAMP, RYNEARSON & ASSOCIATES, INC.
14710 WEST DODGE ROAD, SUITE 100
OMAHA, NEBRASKA 68154-2029

DATE: MAY 12, 2010

The following changes, corrections, clarifications and additions shall be made to the Plans, Specifications, and Contract Documents for the above-named project and shall be as binding as if incorporated in the original Contract Documents. The Contractor shall acquaint himself with all aspects of this Addendum.

All other provisions and stipulations of the Contract Documents remain in effect, as originally issued.

The Contractor shall acknowledge receipt of all addenda on the Proposal Form.

The following shall be deleted, modified or added to as follows:

PLANS

1. Sheet 1 of 38- Revised bid table quantities.
2. Sheet 3 of 38- Added End of Street Apron Detail, revised PCC Paving Note 15 and added PCC Paving Note 18.
3. Sheet 4 of 38- Revised Typical Handicap Striping and Sign Details, added Tree Planting Detail With Rock Drain and added City of Papillion Manhole Detail.
4. Sheet 5 of 38- Revised joint layout.
5. Sheet 6 of 38- Revised Typical Section - Ballpark Way STA 9+52.93 to STA 10+52.93 and Removed Keyed Longitudinal Joint Details.
6. Sheet 8 of 38- Revised Typical Sections – Roundabout.
7. Sheet 10 of 38- Revised End of Pavement Station 25+47.72.
8. Sheet 14 of 38- Revised profile elevations.
9. Sheet 15 of 38- Revised End of Pavement Station 86+54.19 and Begin Pavement Station 90+14.84.
10. Sheet 16 of 38- Revised profile elevations and End of Pavement Station 156+75.00.
11. Sheet 19 of 38- Revised End of Pavement Station 363+21.61 and revised End of Street Area.
12. Sheet 20 of 38- Revised Roundabout Elevations.
13. Sheet 21 of 38- Revised Roundabout Elevations.
14. Sheet 22 of 38- Revised Roundabout Elevations.
15. Sheet 26 of 38- Revised Tape Notes.
16. Sheet 27 of 38- Revised Tape Notes.
17. Sheet 28 of 38- Revised Tape Notes.
18. Sheet 29 of 38- Revised Tape Notes.
19. Sheet 30 of 38- Revised Tape Notes.
20. Sheet 31 of 38- Revised Tape Notes.

CONTRACT DOCUMENTS

1. Replace the bid item tables in the *NOTICE TO CONTRACTORS*, NC-1 to NC-2; *BID DOCUMENTS*, B-1 to B-7; *AGREEMENT*, A-1 to A-8; and *CONTRACTORS APPLICATION FOR PAYMENT* - with the following revised Bid Item Table.

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
1.	REMOBILIZATION	1	EA
2.	9" CONCRETE PAVEMENT - TYPE L65	77,000	SY
3.	7" CONCRETE PAVEMENT - TYPE L65	1,800	SY
4.	COMMON EARTH EXCAVATION	27,467	CY
5.	CONSTRUCT TEMPORARY CURB AND GUTTER (TYPE A)	472	LF
6.	ADJUST MANHOLE TO GRADE	59	EA
7.	EXTERNAL FRAME SEAL	38	EA
8.	MEDIAN SURFACING	4,650	SF
9.	REMOVE TEMPORARY INLET BASE	19	EA
10.	CONSTRUCT CURB INLET - TYPE I	26	EA
11.	CONSTRUCT CURB INLET - TYPE III	21	EA
12.	CONSTRUCT CURB INLET - TYPE IV	1	EA
13.	TAP 18" PIPE INTO EXISTING 60" PIPE	1	EA
14.	MOW STRIP	2,550	SF
15.	CONCRETE HEADER	225	LF
16.	PREFORMED PAVEMENT MARKING TAPE MARKING SYMBOL - WHITE "ONLY"	5	EA
17.	PREFORMED PAVEMENT MARKING TAPE MARKING SYMBOL - WHITE DIRECTIONAL ARROW	31	EA
18.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE, DOTTED	950	LF
19.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE, GROOVED, TYPE 4	7,345	LF
20.	6" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE, GROOVED, TYPE 4	9,950	LF
21.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - YELLOW, GROOVED, TYPE 4	18,000	LF
22.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE, SKIP (10' - 30')	1,400	LF
23.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - YELLOW, SKIP (10' - 30')	3,960	LF
24.	24" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE	950	LF
25.	PREFORMED PAVEMENT MARKING TAPE MARKING SYMBOL - WHITE BIKE SYMBOL	33	EA
26.	PREFORMED PAVEMENT MARKING TAPE MARKING SYMBOL - WHITE BIKE ARROW	33	EA
27.	CONSTRUCT HANDICAP SIGN AND STRIPING	2	EA
28.	BARRICADES - TYPE II	15,000	BD

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
29.	BARRICADES - TYPE III	5,000	BD
30.	CONSTRUCT END OF STREET BARRICADE FOR 25' PAVING	1	EA
31.	CONSTRUCT END OF STREET BARRICADE FOR 47' PAVING	1	EA
32.	JET EXISTING SEWER	9,550	LF
33.	TOPSOIL ISLANDS	505	CY
34.	SEEDING - TYPE "TEMPORARY SEED MIX"	35	AC
35.	STRAW MULCH	35	AC
36.	PINUS FLEXILIS 'PYRAMID' VANDERWOLF PINE B AND B, 5'-6' HIGH MINIMUM	33	EA
37.	CONSTRUCT ROCK ACCESS ROAD	50	TN
38.	CURB INLET PROTECTION	96	EA
39.	CLEANOUT SILT BASIN	1,500	CY
40.	CLEANOUT SILT FENCE	10,000	LF
41.	CLEARING AND GRUBBING GENERAL	1	LS
42.	CLEARING AND GRUBBING TREES OVER 18" TO 27" DIAMETER	11	EA
43.	CUT DOWN 48" TREE AND GRIND STUMP	1	EA
44.	REMOVE, SALVAGE AND REINSTALL BASKETBALL HOOP POLE	1	EA
45.	REMOVE, SALVAGE AND REINSTALL DECORATIVE PARKING METER	1	EA
46.	REMOVE, SALVAGE AND REINSTALL MAILBOX	1	EA
47.	REMOVE SIDEWALK	53	SF
48.	REMOVE DRIVEWAY	141	SY
49.	REMOVE 18" OR SMALLER CULVERT PIPE	50	LF
50.	CONSTRUCT TEMPORARY ROCK ACCESS ROAD	180	TN
51.	CONSTRUCT TEMPORARY ROCK PARKING (4" THICK)	15	TN
52.	CONSTRUCT TEMPORARY MAILBOX	3	EA
53.	STRIP, STOCKPILE, AND RESPREAD TOPSOIL	322	CY
54.	EARTHWORK (EXCAVATION)	677	CY
55.	CONSTRUCT 18" R.C.P., CLASS III	50	LF
56.	CONSTRUCT 18" PIPE BEDDING	50	LF
57.	CONSTRUCT 48" I.D. TYPE II AREA INLET	4	VF
58.	CONSTRUCT 18" R.C. FLARED END SECTION	1	EA
59.	CONSTRUCT 8" CAST IRON DRAIN PIPE	28	LF
60.	CONSTRUCT 4" CAST IRON DRAIN PIPE	25	LF
61.	CONSTRUCT ROCK RIP-RAP - TYPE "A"	3	TON
62.	GENERAL GRADING AND SHAPING	1	LS
63.	7" CONCRETE PAVEMENT - TYPE L6	1,775	SY

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
64.	CONSTRUCT 5" CONCRETE SIDEWALK	54	SF
65.	COMMON EARTH EXCAVATION (FOR L6 CONCRETE)	592	CY
66.	SEEDING - TYPE "NON -IRRIGATED LAWN AND TURF SEED"	1	AC
67.	CONSTRUCT SILT FENCE	410	LF
68.	ROLLED EROSION CONTROL, TYPE II	110	SY
69.	REMOVE SILT FENCE	410	LF

2. Make the following change to the Special Conditions, Section F, Paragraph 17 **CONSTRUCT MEDIAN NOSE**. Delete Paragraph 17 in its entirety and replace with:

17. **CONSTRUCT MEDIAN NOSE**: Concrete median nose shall be constructed as per the City of Omaha standard plate 1-54 and shall be full depth concrete for all of the various radii. Construct median nose shall not be measured and paid for separately, but shall be considered incidental to "Construct _" Concrete Pavement".

3. Make the following change to the Special Conditions, Section F, Paragraph 23 **CONSTRUCT TIE BARS**. Delete Paragraph 23 in its entirety and replace with:

23. **CONSTRUCT TIE BARS**: At the locations indicated in the PLANS, contractor shall construct tie bars in accordance with the notes on the PLANS. Construct tie bars shall not be measured and paid for separately, but shall be considered incidental to "Construct _" Concrete Pavement".

REVISED BID FORM ENCLOSED

ENCLOSURES

END OF ADDENDUM



Sincerely,

LAMP, RYNEARSON & ASSOCIATES, INC.

A handwritten signature in black ink, appearing to read "Christopher J. Langan".

Chris Langan, P.E.
 Senior Project Engineer