

NOTICE TO CONTRACTORS

Sealed Bids will be received by SANITARY AND IMPROVEMENT DISTRICT NO. 290 at the office of Lamp, Ryneason & Associates, Inc., 14710 WEST DODGE ROAD, SUITE 100, OMAHA, NEBRASKA, until 4:30 P.M. MAY 18, 2010, for furnishing all labor, tools, materials, and equipment required for the project designated as PAVING, SECTION I, and all other work necessary or incidental thereto, as per plans and specifications on file at the office of said Engineer, at which time Bids will be publicly opened, read aloud, and tabulated. The extent of the work involved and the materials to be bid upon are as follows:

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
1.	REMOBILIZATION	1	EA
2.	9" CONCRETE PAVEMENT - TYPE L65	77,000	SY
3.	7" CONCRETE PAVEMENT - TYPE L65	1,800	SY
4.	COMMON EARTH EXCAVATION	27,467	CY
5.	CONSTRUCT TEMPORARY CURB AND GUTTER (TYPE A)	472	LF
6.	ADJUST MANHOLE TO GRADE	59	EA
7.	EXTERNAL FRAME SEAL	38	EA
8.	MEDIAN SURFACING	4,650	SF
9.	REMOVE TEMPORARY INLET BASE	19	EA
10.	CONSTRUCT CURB INLET - TYPE I	26	EA
11.	CONSTRUCT CURB INLET - TYPE III	21	EA
12.	CONSTRUCT CURB INLET - TYPE IV	1	EA
13.	TAP 18" PIPE INTO EXISTING 60" PIPE	1	EA
14.	MOW STRIP	2,550	SF
15.	CONSTRUCT MEDIAN NOSE	30	EA
16.	CONCRETE HEADER	225	LF
17.	CONSTRUCT TIE BARS	210	EA
18.	PREFORMED PAVEMENT MARKING TAPE MARKING SYMBOL - WHITE "ONLY"	5	EA
19.	PREFORMED PAVEMENT MARKING TAPE MARKING SYMBOL - WHITE DIRECTIONAL ARROW	31	EA
20.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE, DOTTED	950	LF
21.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE, GROOVED, TYPE 4	7,345	LF
22.	6" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE, GROOVED, TYPE 4	9,950	LF
23.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - YELLOW, GROOVED, TYPE 4	18,000	LF
24.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE, SKIP (10' - 30')	1,400	LF
25.	5" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - YELLOW, SKIP (10' - 30')	3,960	LF
26.	24" PREFORMED PAVEMENT MARKING TAPE PAVEMENT MARKING - WHITE	950	LF
27.	PREFORMED PAVEMENT MARKING TAPE MARKING SYMBOL - WHITE BIKE SYMBOL	33	EA
28.	PREFORMED PAVEMENT MARKING TAPE MARKING SYMBOL - WHITE BIKE ARROW	33	EA
29.	CONSTRUCT HANDICAP SIGN AND STRIPING	2	EA
30.	BARRICADES - TYPE II	15,000	BD

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
31.	BARRICADES - TYPE III	5,000	BD
32.	CONSTRUCT END OF STREET BARRICADE FOR 25' PAVING	1	EA
33.	CONSTRUCT END OF STREET BARRICADE FOR 47' PAVING	1	EA
34.	JET EXISTING SEWER	9,550	LF
35.	TOPSOIL ISLANDS	505	CY
36.	SEEDING - TYPE "TEMPORARY SEED MIX"	35	AC
37.	STRAW MULCH	35	AC
38.	PINUS FLEXILIS 'PYRAMID' VANDERWOLF PINE B AND B, 5'-6' HIGH MINIMUM	33	EA
39.	CONSTRUCT ROCK ACCESS ROAD	50	TN
40.	CURB INLET PROTECTION	96	EA
41.	CLEANOUT SILT BASIN	1,500	CY
42.	CLEANOUT SILT FENCE	10,000	LF
43.	CLEARING AND GRUBBING GENERAL	1	LS
44.	CLEARING AND GRUBBING TREES OVER 18" TO 27" DIAMETER	11	EA
45.	CUT DOWN 48" TREE AND GRIND STUMP	1	EA
46.	REMOVE, SALVAGE AND REINSTALL BASKETBALL HOOP POLE	1	EA
47.	REMOVE, SALVAGE AND REINSTALL DECORATIVE PARKING METER	1	EA
48.	REMOVE, SALVAGE AND REINSTALL MAILBOX	1	EA
49.	REMOVE SIDEWALK	53	SF
50.	REMOVE DRIVEWAY	141	SY
51.	REMOVE 18" OR SMALLER CULVERT PIPE	50	LF
52.	CONSTRUCT TEMPORARY ROCK ACCESS ROAD	180	TN
53.	CONSTRUCT TEMPORARY ROCK PARKING (4" THICK)	15	TN
54.	CONSTRUCT TEMPORARY MAILBOX	3	EA
55.	STRIP, STOCKPILE, AND RESPREAD TOPSOIL	322	CY
56.	EARTHWORK (EXCAVATION)	677	CY
57.	CONSTRUCT 18" R.C.P., CLASS III	50	LF
58.	CONSTRUCT 18" PIPE BEDDING	50	LF
59.	CONSTRUCT 48" I.D. TYPE II AREA INLET	4	VF
60.	CONSTRUCT 18" R.C. FLARED END SECTION	1	EA
61.	CONSTRUCT 8" CAST IRON DRAIN PIPE	28	LF
62.	CONSTRUCT 4" CAST IRON DRAIN PIPE	25	LF
63.	CONSTRUCT ROCK RIP-RAP - TYPE "A"	3	TON
64.	GENERAL GRADING AND SHAPING	1	LS
65.	7" CONCRETE PAVEMENT - TYPE L6	1,775	SY
66.	CONSTRUCT 5" CONCRETE SIDEWALK	54	SF
67.	COMMON EARTH EXCAVATION (FOR L6 CONCRETE)	592	CY
68.	SEEDING - TYPE "NON -IRRIGATED LAWN AND TURF SEED"	1	AC
69.	CONSTRUCT SILT FENCE	410	LF
70.	ROLLED EROSION CONTROL, TYPE II	110	SY
71.	REMOVE SILT FENCE	410	LF

Upon approval, the Owner will issue payment to the Contractor in the amount of 90% of the contracted value of the completed work as of the end of the preceding month, as recommended by the Engineer. Payment for the balance retained will be issued by the Owner upon completion of the work and approval thereof by the Owner's Engineer, City or Governmental approval when necessary, and acceptance by the Owner.

A set of plans and specifications may be obtained from the Engineer upon payment of \$44.00 (prepaid) if picked up and \$51.00 (prepaid) if mailed, no part of which will be refunded. All Bids must be submitted on forms furnished by said Engineer, and must be enclosed in a sealed envelope, addressed to SANITARY AND IMPROVEMENT DISTRICT NO. 290 OF SARPY COUNTY, NEBRASKA c/o said Engineer.

Each bid shall be accompanied, in a separate sealed envelope, by a certified or bank check drawn on a bank whose deposits are insured by the F.D.I.C. or an acceptable bid bond in the amount of ONE HUNDRED FIFTY-THREE THOUSAND, SIX HUNDRED EIGHTY-FIVE AND NO/100 DOLLARS (\$153,685.00) and shall be payable without condition to SANITARY AND IMPROVEMENT DISTRICT NO. 290 as a guarantee that the bidder, if successful, will execute the contract and provide an acceptable Contract Bond from an approved surety in the amount of 100 percent of the contract price. No bidder may withdraw his Bid for a period of THIRTY (30) days after the date set for the opening of bids. The Owner reserves the right to reject any or all bids and to waive informalities.

LAMP, RYNEARSON & ASSOCIATES, INC.



Brett J. Wawers, P.E.
Senior Vice President

Job Site: SCHEWE FARMS
PAVING, SECTION I
120TH STREET AND HIGHWAY 370
0109050.11-050/350