

NOTICE TO CONTRACTORS

Sealed Bids will be received by SANITARY AND IMPROVEMENT DISTRICT NO. 290 OF SARPY COUNTY, NEBRASKA at the office of Lamp, Rynearson & Associates, Inc., 14710 WEST DODGE ROAD, SUITE 100, OMAHA, NEBRASKA, until 4:30 P.M. APRIL 27, 2010, for furnishing all labor, tools, materials, and equipment required for the project designated as STORM SEWER, SECTION I AND SANITARY SEWER, SECTION II (SCHEWE FARMS), and all other work necessary or incidental thereto, as per plans and specifications on file at the office of said Engineer, at which time Bids will be publicly opened, read aloud, and tabulated. The extent of the work involved and the materials to be bid upon are as follows:

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
	STORM SEWER, SECTION I		
1.	REMOBILIZATION	1	EA
2.	CLEARING AND GRUBBING GENERAL	1	LS
3.	GENERAL GRADING AND SHAPING	1	LS
4.	EARTHWORK (EXCAVATION)	16,425	CY
5.	MAINTAIN ROCK ACCESS ROAD	100	TN
6.	REMOVE 18" C.M.P.	675	LF
7.	REMOVE RIP RAP APRON	40	TN
8.	FLOWABLE FILL	16	CY
9.	CONSTRUCT 15" R.C.P., CLASS III	1,500	LF
10.	CONSTRUCT 18" R.C.P., CLASS III	1,750	LF
11.	CONSTRUCT 24" R.C.P., CLASS III	600	LF
12.	CONSTRUCT 27" R.C.P., CLASS III	50	LF
13.	CONSTRUCT 30" R.C.P., CLASS III	950	LF
14.	CONSTRUCT 36" R.C.P., D(0.01) = 1,350	2,100	LF
15.	CONSTRUCT 42" R.C.P., D(0.01) = 1,350	2,500	LF
16.	CONSTRUCT 48" R.C.P., D(0.01) = 1,350	400	LF
17.	CONSTRUCT 54" R.C.P., D(0.01) = 1,350	1,300	LF
18.	CONSTRUCT 60" R.C.P., D(0.01) = 1,350	1,100	LF
19.	CONSTRUCT 66" R.C.P., D(0.01) = 1,350	90	LF
20.	CONSTRUCT 72" R.C.P., D(0.01) = 1,350	80	LF
21.	CONSTRUCT 48" R.C.P., D(0.01) = 1,350 WITH PIPE COUPLERS	45	LF
22.	CONSTRUCT 54" R.C.P., D(0.01) = 1,350 WITH PIPE COUPLERS	85	LF
23.	CONSTRUCT 18" C.M.P.	250	LF
24.	CONSTRUCT SALVAGED 18" C.M.P.	225	LF
25.	CONSTRUCT 54" I.D. FLATTOP MANHOLE (4 EA)	25	VF
26.	CONSTRUCT 66" I.D. FLATTOP MANHOLE (10 EA)	70	VF
27.	CONSTRUCT 72" I.D. FLATTOP MANHOLE (6 EA)	55	VF
28.	CONSTRUCT 84" I.D. FLATTOP MANHOLE (7 EA)	65	VF
29.	CONSTRUCT 96" I.D. FLATTOP MANHOLE (4 EA)	40	VF
30.	CONSTRUCT 108" I.D. FLATTOP MANHOLE (6 EA)	80	VF
31.	CONSTRUCT MANHOLE RING COLLAR	19	EA
32.	CONSTRUCT 54" I.D. TYPE II AREA INLET (7 EA)	50	VF
33.	CONSTRUCT 72" I.D. TYPE II AREA INLET (1 EA)	9	VF

ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
34.	CONSTRUCT 72" I.D. TYPE II AREA INLET (12" OPENING) (1 EA)	9	VF
35.	CONSTRUCT CURB INLET - TYPE III WITH APRON	2	EA
36.	CONSTRUCT TEMPORARY INLET BASE	19	EA
37.	CONSTRUCT PCC COLLAR	2	EA
38.	CONSTRUCT 15" PIPE BEDDING	1,500	LF
39.	CONSTRUCT 18" PIPE BEDDING	1,750	LF
40.	CONSTRUCT 24" PIPE BEDDING	1,750	LF
41.	CONSTRUCT 27" PIPE BEDDING	50	LF
42.	CONSTRUCT 30" PIPE BEDDING	950	LF
43.	CONSTRUCT 36" PIPE BEDDING	2,100	LF
44.	CONSTRUCT 42" PIPE BEDDING	2,500	LF
45.	CONSTRUCT 48" PIPE BEDDING	445	LF
46.	CONSTRUCT 54" PIPE BEDDING	1,385	LF
47.	CONSTRUCT 60" PIPE BEDDING	1,100	LF
48.	CONSTRUCT 66" PIPE BEDDING	90	LF
49.	CONSTRUCT 72" PIPE BEDDING	80	LF
50.	TAP EXISTING 54" I.D. FLATTOP MANHOLE	2	EA
51.	TAP EXISTING 66" I.D. FLATTOP MANHOLE	2	EA
52.	TAP EXISTING 84" I.D. FLATTOP MANHOLE	2	EA
53.	TAP EXISTING 96" I.D. FLATTOP MANHOLE	3	EA
54.	CONSTRUCT 18" R.C. VERTICAL PIPE BEND	2	EA
55.	CONSTRUCT 18" R.C. HORIZONTAL AND VERTICAL PIPE BEND	6	EA
56.	CONSTRUCT 48" R.C. FLARED END SECTION	2	EA
57.	CONSTRUCT 54" R.C. FLARED END SECTION	2	EA
58.	CONSTRUCT 66" R.C. FLARED END SECTION	1	EA
59.	CONSTRUCT TIMBER PILE PIPE SUPPORT (54" - 72")	1	EA
60.	CONSTRUCT 15" R.C.P. PIPE PLUG	2	EA
61.	CONSTRUCT 18" R.C.P. PIPE PLUG	2	EA
62.	CONSTRUCT 24" R.C.P. PIPE PLUG	4	EA
63.	CONSTRUCT 27" R.C.P. PIPE PLUG	1	EA
64.	CONSTRUCT 30" R.C.P. PIPE PLUG	2	EA
65.	CONSTRUCT 36" R.C.P. PIPE PLUG	7	EA
66.	CONSTRUCT 42" R.C.P. PIPE PLUG	7	EA
67.	CONSTRUCT ROCK RIP RAP - TYPE B	100	TN
68.	CONSTRUCT ROCK RIP RAP - TYPE C	200	TN
69.	CONSTRUCT GABIONS AND REVET MATTRESS	120	CY
70.	CONSTRUCT TEMPORARY PIPE DIVERSION (18" - 27")	1	EA
71.	STABILIZE TRENCH WITH CRUSHED LIMESTONE	500	TN
72.	CONSTRUCT LONG-TERM EROSION CONTROL BLANKET	5,500	SY
73.	CONSTRUCT INLET FILTER	400	LF
74.	CONSTRUCT SILT FENCE	1,000	LF
75.	CLEANOUT SILT FENCE	500	LF
76.	REMOVE SILT FENCE	2,200	LF


ITEM NO.	BID ITEM DESCRIPTION	APPROXIMATE QUANTITY	
77.	SEEDING - TYPE "A"	1.0	AC
78.	SEEDING - TYPE "B"	1.0	AC
79.	SEEDING - TYPE "T"	4.0	AC
80.	SEEDING - TYPE "W"	0.3	AC
81.	STRAW MULCH	4.0	AC
	SANITARY SEWER, SECTION II		
82.	REMOVE 8" PIPE PLUG	6	EA
83.	CONSTRUCT 8" SANITARY SEWER PIPE	1,450	LF
84.	CONSTRUCT 8" PIPE BEDDING	1,450	LF
85.	CONSTRUCT 8" PIPE PLUG	3	EA
86.	TRENCH INSULATION	70	LF
87.	CONSTRUCT 54" I.D. SANITARY MANHOLE (2 EA)	30	VF

Upon approval, the Owner will issue payment to the Contractor in the amount of 90% of the contracted value of the completed work as of the end of the preceding month, as recommended by the Engineer. Payment for the balance retained will be issued by the Owner upon completion of the work and approval thereof by the Owner's Engineer, City or Governmental approval when necessary, and acceptance by the Owner.

A set of plans and specifications may be obtained from the Engineer upon payment of \$30.00 (prepaid) if picked up and \$37.00 (prepaid) if mailed, no part of which will be refunded. All Bids must be submitted on forms furnished by said Engineer, and must be enclosed in a sealed envelope, addressed to SANITARY AND IMPROVEMENT DISTRICT NO. 290 OF SARP COUNTY, NEBRASKA c/o said Engineer.

Each bid shall be accompanied, in a separate sealed envelope, by a certified or bank check drawn on a bank whose deposits are insured by the F.D.I.C. or an acceptable bid bond in the amount of \$61,180.00 and shall be payable without condition to SANITARY AND IMPROVEMENT DISTRICT NO. 290 OF SARP COUNTY, NEBRASKA as a guarantee that the bidder, if successful, will execute the contract and provide an acceptable Contract Bond from an approved surety in the amount of 100 percent of the contract price. No bidder may withdraw his Bid for a period of THIRTY (30) days after the date set for the opening of bids. The Owner reserves the right to reject any or all bids and to waive informalities.

LAMP, RYNEARSON & ASSOCIATES, INC.


Brett J. Wawers, P.E.
Senior Vice President

Job Site: STORM SEWER, SECTION I AND SANITARY SEWER, SECTION II (SCHEWE FARMS)
120TH STREET & HIGHWAY 370
0109050.11-040/340